

**VAN WYK'S**



**ELECTRICAL**

141 Station Rd  
Brakpan  
1541  
www.vwe.co.za  
REG. Number 1983/007915/07

P.O. Box 14534  
Farrarmere  
1518  
Tel : 011 740 1238  
Fax : 011 740 1268

Directors : M. Van Wyk, T. Van Wyk

Date : 22 January 2011

---

## Conformance to SANS 61439:2009 Parts 1 and 2

---

This serves to confirm that Van Wyk's Electrical (Pty) Ltd conducted low voltage switchgear and controlgear ASSEMBLY Type Testing at SABS NETFA during August and September 2010 in accordance with SANS 61439-1:2009 parts 1 and 2 annex D items 1-5 and 9-11 for compliance with designated verification tests.

By way of verification, we attach a schedule of the tests that were conducted together with the results that were obtained.

---





# VAN WYK'S ELECTRICAL

Assembly Testing Sequence for Compliance with SANS 61439:2009 Parts 1 & 2

Test no	Test Description	Date	Test data	Result	Comment
1	Impulse voltage withstand	4.08.2010	As per SANS 61439-1 for 8kV sea level applications	Complied	
2	ASSEMBLY Temperature-rise IP3X	10.08.2010	Initial testing failed due to various circumstance beyond our control	Fail	SANS interconnections were damaged and the replacement prevented current balance being achieved.
3	ASSEMBLY Temperature-rise IP3X re-test	25.08.2010	Test current set at 2750 amps	Complied	MG top centre pole temperature-rise of 79.83K (80K limit) limited the test current
4	ASSEMBLY Temperature-rise IP4X re-test	25.08.2010	Test current set at 2400amps	Complied	MG top centre pole temperature-rise of 76.93K (80K limit) limited the test current. Current could have been set marginally higher at 2500 amps
5	Short-circuit withstand	31.08.2010	Main busbar structure 50kA 1 second	Complied	Temperature-rise star point removed ACB rear bridges installed Dropper busbar bridge installed All other outgoing circuit bridges installed
6	Short-circuit withstand	31.08.2010	Neutral busbar structure 30kA 1 second	Complied	REMOVE dropper busbar star-point bridge ASSEMBLY repositioned to enable neutral to be connected to a phase
7	Short-circuit withstand	31.08.2010	PE busbar structure 30kA 1 second	Complied	PE conductor connected to TWO phased by means of cables
8	Conditional short-circuit withstand 400V+10% 50kA	1.09.2010	1600A feeder in section D2	80kA Peak 77.9 kA peak 44.85kA peak 13.8ms	ASSEMBLY repositioned to enable three phases to be connected to test rig CLOSE 1600A circuit breaker for test
9	Conditional short-circuit withstand 400V+10% 50kA	1.09.2010	630A feeder in section B8	29.04kA peak 38.14 kA peak 20.97kA peak 7.2ms	CLOSE 630A circuit breaker for test
10	Conditional short-circuit withstand 525+10% 50kA	1.09.2010	110kW motor starter combination in section B5	17.17kA peak 25.08kA peak 14.58kA peak 6.36ms	CLOSE circuit breaker and activate contactor for test
11	Conditional short-circuit withstand 525+10% 50kA	1.09.2010	75kW motor starter combination in section B7	14.67kA peak 23.12kA peak 14.14kA peak 6.42ms	CLOSE circuit breaker and activate contactor for test
12	Conditional short-circuit withstand 525+10% 50kA	1.09.2010	45kW motor starter combination in section B4	12.6kA peak 19kA peak 11.48kA peak 6.66ms	CLOSE circuit breaker and activate contactor for test
13	Conditional short-circuit withstand 525+10% 50kA	1.09.2010	15kW motor starter combination in section B3	9.91kA peak 14.7kA peak 9.25kA peak 6.48ms	CLOSE circuit breaker and activate contactor for test
14	Conditional short-circuit withstand 525+10% 50kA	2.09.2010	Incoming Merlin Gerin ACB in section A2	98.77kA peak 74.12kA peak 22.85kA peak 56.94ms	Remove Incoming MG circuit breaker bridges and re-torque connections & check. Re-install dropper busbar bridges Close ACB switch
15	Repeat short-circuit withstand test on main busbar structure with intermediate busbar supports removed	2.09.2010	Main busbar structure 50kA 1 second	Complied	Temperature-rise star point removed ACB rear bridges installed Dropper busbar bridge installed All other outgoing circuit bridges installed
16	Repeat short-circuit withstand test on neutral busbar structure with intermediate busbar supports removed	2.09.2010	Neutral busbar structure 30kA 1 second	Complied	REMOVE dropper busbar star-point bridge ASSEMBLY repositioned to enable neutral to be connected to a phase
17	Dielectric test to verify functional unit compliance with on completion of testing	2.09.2010	All outgoing functional unit SCPD□fs	Complied	
18	IP3X / I4X verification		2.5mm & 1mm probes	Complied	
19	Internal degree of separation IP2X		12mm finger probe	Complied	
20	Verification of the effective connection between conductive parts of the ASSEMBLY and the protective circuit		≤ 0.1Ω with a 10A resistance measuring instrument	Complied	
21	Glow-wire test on busbar support material		IEC60695-2-10/11 960°C	Complied	